

GPC Services Ltd

Quotation Sheet



GPC Services Ltd
 11a, Hall Lane,
 Coventry,
 CV2 2AU

Date: 03/10/2025

Quotation Number: GPC: 00942

Location: Stanton under Bardon Parish Council

Quotation Valid until: 02/12/2025

Prepared By: Julia Burrows

Price: SEE BELOW

Dear Customer, thank you for your enquiry and we are glad to enclose the following quotation

Stanton under Bardon Parish Council

Joanne Lowe

Job 1

To supply the labour and machinery to excavate the existing Breedon gravel pathways to the depth of 50mm to remove all overgrown vegetation. All waste will be spread around the grounds. Supply and install new Breedon gravel aggregate to the existing pathways and compact. (Existing pathways are 310m by 1.6m with timber edging each side. No allowance has been made to replace any timber edgings).

Total Price £9,800+VAT

Job 2

(New Breedon gravel pathway from the existing pathway to the dog waste bin as per drawing provided).

To supply the labour and machinery to excavate new pathway to a depth of 150mm install timber edging either side of the pathway. Install weed prove membrane to the area and install 100mm of type 1 road stone and compact. Install 50mm of Breedon gravel aggregate and compact.

(New pathway is 80m long by 1.6m wide)

Total Price £ 8,966+VAT

Optional extra

(New Breedon gravel pathway from the dog waste bin around the fruit tree to the exiting pathway to the corner of the Muga).

To supply the labour and machinery to excavate new pathway to a depth of 150mm install timber edging either side of the pathway. Install weed prove membrane to the area and install 100mm of type 1 road stone and compact. Install 50mm of breedon gravel aggregate and compact.

(New pathway is 143m long by 1.6m wide)

Total Price £16,016+VAT

Yours Sincerely,
 Gerald Peter Coulson

If you have any questions concerning this quotation contact Gerald Coulson,

Email : info@gpcservicesltd.co.uk

Mobile 07956829154

THANK YOU FOR YOUR BUSINESS!

GPC Garden Services Limited is a company registered in England and Wales - 06078075

Registered Office – 11a Hall Lane, Walsgrave, Coventry CV2 2AU

VAT Registration Number - GB876445483

Quote To:

Joanne -

Stanton Under
Bardon Clerk

Project Address:

Stanton Under Bardon
Recreational Grounds
Main Street
LE67 9AB

Quotation

Quote No: 0642

Date: 05/10/25

DESCRIPTION	MATERIAL	LABOUR	SUBTOTAL
JOB DESCRIPTION -INSTALLATION OF NEW PATHWAY TO DDA REGULATIONS.			
Create a safe compound with use of heras panels.			
Excavate new area by way of machinery, creating a 78m long x 1.5m wide pathway. Dug down to approx 200mm below finished height	30t Type 1 MOT		
Supply and install new 6x1" timbers to create new edging 1.5m wide.	15t Breedon self binding gravel	Approx. 8 working days - dependant on factors out of our control.	£13,850.00 + VAT
Supply and install type 1 MOT approximately 150mm deep and compact.	70 x 6x1" @ 3m length of treated timber		
Supply and install 50mm of Breedon self binding gravel to match existing pathways	Machinery hire		
Roll / compact new gravel by way of machinery	Waste removal		
Finish and tidy work area, dismantle compound.			
Removal of all associated waste.			
		SUBTOTAL	£13,850.00
		VAT @ 20%	£2,770.00
		TOTAL	£16,620.00

ANY ADDITIONAL WORK NOT DETAILED ABOVE WILL BE SUBJECT TO YOUR APPROVAL PRIOR TO THE WORK BEING CARRIED OUT.

IF YOU REQUIRE ANY FURTHER INFORMATION PLEASE DO NOT HESITATE TO CONTACT US.

QUOTATION VALID FOR **30 DAYS** FROM DATE OF QUOTATION



01509 351050 | 07525769012



Hello@montislandscapes.co.uk



www.montislandscapes.co.uk



Quote To:

Joanne -

Stanton Under
Bardon Clerk

Project Address:

Stanton Under Bardon
Recreational Grounds
Main Street
LE67 9AB

Quotation

Quote No: 0641

Date: 05/10/25

DESCRIPTION	MATERIAL	LABOUR	SUBTOTAL
JOB DESCRIPTION - REINSTATING EXISTING PATHWAYS BACK TO DDA REGULATIONS, 1.5M WIDE. BASED ON 312 LINEAR METRES. Create a safe compound with use of heras panels. Scrape back all vegetation on existing pathway and remove approx 30mm of top dressing gravel and remove from site. Remove all damaged timber edging and remove from site. Supply and install new 6x1" timbers to create new edging 1.5m wide Supply and install 30mm of Breedon self binding gravel to existing pathways. Roll / compact new gravel by way of machinery Finish and tidy work area, dismantle compound. Removal of all associated waste.	40t Breedon self binding gravel 300 x 6x1" @ 3m length of treated timber Machinery hire Waste removal	Approx. 12 working days - dependant on factors out of our control.	£20,580.00 + VAT
		SUBTOTAL	£10,580.00
		VAT @ 20%	£4,116.00
		TOTAL	£24,696.00

ANY ADDITIONAL WORK NOT DETAILED ABOVE WILL BE SUBJECT TO YOUR APPROVAL PRIOR TO THE WORK BEING CARRIED OUT.

IF YOU REQUIRE ANY FURTHER INFORMATION PLEASE DO NOT HESITATE TO CONTACT US.

QUOTATION VALID FOR **30 DAYS** FROM DATE OF QUOTATION



01509 351050 | 07525769012



Hello@montislandscapes.co.uk



www.montislandscapes.co.uk





BURNT OAK DEVELOPMENTS

| PROPERTY | LAND | AGRICULTURE |

Burnt Oak Developments Limited
29 Ruskin Avenue
Syston
Leicestershire
LE7 2BY

Tel: 01664 373498 – 07752 132997
Email: office@burntoakdevelopments.co.uk
www.burntoakdevelopments.co.uk

Stanton under Bardon Parish Council
Attention: Joanne Lowe
Village Hall
St John Cole Crescent
Stanton under Bardon
Leicestershire
LE67 9AE

Estimate Number Estimate -0615
Estimate Date 06 Oct 2025
Expiry Date 05 Nov 2025
Account Ref SUBAPC01
Reference

ESTIMATE

Renovation and installation of pathways

To renovate existing stone-topped pathways around the recreation ground, to bring back to 1.2m wide for wheelchair access, redress topping. Also for the addition of new pathway to the footpath gate on the East side of the park.

Description	Quantity	Unit Price	VAT	Amount GBP
Existing pathways to be stripped back, removing all weeds and contamination from the surface allowing for 50mm of new self-binding gravel to be added. Finished surface to be water rolled to provide correct binding finish.				
New pathway to be added, 1.2m wide over the whole 75m length. Area to be dug out to a minimum of 150mm deep to allow for sufficient sub-base. Timber edging to be added either side to match with existing pathways, held with wooden pegs every metre. Geotextile membrane laid first to provide additional support for MOT type 1 sub-base, compacted to leave 50mm for Breedon Golden Amber self-binding gravel. Again all finished surface to be water rolled to provide proper adhesion.	1.00	12,993.40	20%	12,993.40
NOTE: This does not include removal of waste from site				
Additional cost for dig-out waste removal from site	1.00	1,200.00	20%	1,200.00
			Subtotal	14,193.40
			Total VAT 20%	2,838.68
			TOTAL GBP	17,032.08

Terms

Proud Member Of:



Registered in England and Wales No: 8444455
VAT Reg No: 171425621

Proud Member Of:



Registered in England and Wales No: 8444455
VAT Reg No: 171425621