

ITEMS LIST

- Play Equipment**
- 1. Metal Combination Swing: 1x Me to You 1x Cradle (2.0m High frame) Ref: UK41385P2200
 - 2. Diabolo Multipay Unit Ref: J3835A-C
 - 3. The Cottage Playhouse Ref: J235A
 - 4. Low Platform Roundabout Ref: J2404A
 - 5. Four Seat Spring Snee Snee Ref: J63A
 - 6. Little Steps Ref: J12A
 - 7. The Flowers Board Play Panel Ref: J3402*
 - 8. Play Panel - What time is it? Ref: J3423**
- * Includes 2 x G3423A Posts
** Includes 2 x G3425A Posts

- Ancillaries**
- 9. 40Lm Bowtop Fence 1M High Galvanised Ref: UKN1000
 - 10. 1.0m High Hydraulic Self Closing Gate (Hinged Left) - Yellow Ref: UKN1101

- Existing Play Equipment (Relocated)**
- 11. Falling Star Spring Ref: J820A
 - 12. The Horse Spring Ref: J857A

- Existing Play Equipment**
- 13. Ino Multipay Unit

- Existing Ancillaries**
- 14. Picnic Bench

Safety Surfacing
Area to be surfaced with 161m² Grassmat.

- Groundworks**
- 19m² Spoil from excavations to be used to backfill void where Wetpour & Springers have been removed to correct finished levels.
 - Supply & Lay 19m² Topsoil & Turf (Watering not included) where Wetpour & Springers have been removed.

Removals
Dig removal of existing Flat Seat Swings, 2 x Springers (to be relocated) 17m² Wetpour including Stone Subbase & 10Lm PCC edges.

- Miscellaneous**
- Preliminaries included
 - Post Installation Inspection included

Based on a flat fully established grass site.

Proposed Grassmat Safer surfacing is based on a fully established grass site (including a minimum of 150mm of good quality soil and turf).

Proposed Grassmat will follow the natural contours of the land.


Preliminaries have been included within your quotation, these equate to site setup, safety fencing, safety signage, welfare, offloading of equipment, storage & waste removal.

All pathways, furniture, planting, mounding and any other soft landscaping works not mentioned above are to be done by others.

Some images shown are for illustrative purposes only. The quote and items list will show the exact equipment used.

SURFACING DETAIL

Not to Scale



PRODUCT KEY



Heddon Welfare Field Phase 1

Heddon on the Wall Parish Council

DATE: 16/08/2024 REF: 2408.44158(Heddon_Welfare_Field_HOTWPC)

REV: DB: PP CB: KA SCALE: 1:100 @ A3



ITEMS LIST

Play Equipment

- 1. Rollercoaster Ref: J3501A
- 2. Rollup Ref: J2591A
- 3. Junior Metal Parallel Bars Ref: JPS15A-JM
- 4. Metal Trim Trail Junior Wall Bars Ref: JPS11A-JM
- 5. Metal Balance Beam Ref: JPS14A-M
- 6. Metal Flat Seat Swing (2.00m high frame) Ref: J472A

Existing Play Equipment

- 7. Pod Swing Ref: J441A
- 8. Double Parch Ref: J395A
- 9. Climbing Net Ref: J4815A
- 10. Top Multipay Unit
- 11. Mound Slide

Safety Surfacing
Area to be surfaced with 101m² Grassmat.
Item 11 Mound Slide to be surfaced with 20m² Green Bonded Rubber Mulch with 1m² Standard Green Wetpour wear pad to a CFH of 1.2m.

Groundworks
Rubber Mulch onto the existing re-shaped mound requires the following groundworks:

- 2m² Imported Topsoil to be used to backfill void where existing Rubber Tiles have been removed and where existing mound has been eroded to restore correct levels.
- 20m² MOT Type 1 Stone up to 50mm Deep
- 20m² Concrete Cap to a depth of 75mm
- 22m² Chase Cut Edging into Grass etc. backfill & re-installment with seed / re-use existing turf

Re-installment

- 4m² Imported Topsoil to be used to backfill void where existing Wetpour has been removed to restore correct levels.
- Supply & Lay 22m² Topsoil & Turf

Remove

- Dig removal of existing Cradle Seat Swings & 28Lm PPC edges
- 22m² Wetpour including Stone Subbase
- 4m² Rubber Tiles & Concrete Subbase

Miscellaneous

- Preliminaries included
- Pod Installation inspection included

Added Value
Added Value Spaces - Replacement TMSABN Net Component FREE OF CHARGE

Based on a flat fully established grass site.

Proposed Grassmat Safer surfacing is based on a fully established grass site (including a minimum of 150mm of good quality soil and turf).

Proposed Grassmat will follow the natural contours of the land.

Rubber Mulch price based on a well draining site, any additional drainage required (French drains or soak aways) will be at an additional cost.

All Rubber Mulch colours are subject to ultra violet light degradation and as such total colour stability cannot be guaranteed. Consistency of shade or pigment in this recycled product cannot be guaranteed. Coloured Coated Surfaces may lose their coating and pigment from this recycled product may come off on clothes and cause staining.

Preliminaries have been included within your quotation, these equate to site setup, safety fencing, safety signage, welfare, offloading of equipment, storage & waste removal.

All pathways, furniture, planting, mounding and any other soft landscaping works not mentioned above are to be done by others.

Subject to further survey from a Proludic Representative to assess. Precise dimensions and location of existing mound slide and associated safer surfacing.

Some images shown are for illustrative purposes only. The quote and items list will show the exact equipment used.

PRODUCT KEY

Existing Grass	Grassmat
Existing Path	Existing HUGA
Topsoil & Turf	Existing Bonded Rubber Mulch
New Bonded Rubber Mulch	Chase Cut into Grass
Existing Mound (re-shaped mound)	Free Fall
Free Fall	Free Space

Heddon Welfare Field Phase 2

Heddon on the Wall Parish Council

DATE: 19/08/2024 REF: 2408.44161(Heddon_Welfare_Field_P2HOTWPC)
 REV: - DB: PP CB: AL SCALE: 1:150 @ A3

